Technical Specifications of Items/BoQ

S. No.	Item	Description
1.1	Indoor Camera	2 MP / 30M IR Fixed Bullet Network Camera • 1/2.8" CMOS • 1920 ×1080@30fps • fixed lens • H.265+ • Three streams • 120dB WDR • 2 Behavior analyses, and face detection • BLC/3D DNR/ROI • IP67 • Built-in micro SD/SDHC/SDXC card slot
1.2	Outdoor Camera	2 MP / 80M IR Fixed Bullet Network Camera • 1/2.8" CMOS • 1920 ×1080@30fps • fixed lens • H.265+ • Three streams • 120dB WDR • 2 Behavior analyses, and face detection • BLC/3D DNR/ROI • IP67 • Built-in micro SD/SDHC/SDXC card slot
2.1	16 channel NVR	4K NVR with 2 SATA interfaces • Third-party network cameras supported • Support 1-ch HDMI, 1-ch VGA, HMDI at up to 4K(3840x2160) resolution • 160Mbps incoming bandwidth • Support H.265/H.264/MPEG4 video formats
2.2		4K NVR with 2 SATA interfaces • Third-party network cameras supported • Support 1-ch HDMI, 1-ch VGA, HMDI at up to 4K(3840x2160) resolution

	32 channel NVR	• 256Mbps incoming bandwidth • Support H.265/H.264/MPEG4 video formats
2.3	64 channel NVR	4K NVR with 8 SATA interfaces • Third-party network cameras supported • Support 2-ch HDMI, 2-ch VGA, HMDI1 at up to 4K(3840x2160) resolution • 320Mbps incoming bandwidth • Support HDD hot swap with RAID0,1,5,6,10 storage scheme configurable •Support H.265/H.264/MPEG4 video formats
3	Hard Disk	4TB Surveillance Hard Disk
4	Cabling	Pure Copper 23AWG CAT6 (ISO Certificated) Branded Power Cable 3/29 Black/Red, (ISO Certificated) including Branded PVC Pipe and Dura duck (ISO Certificated) /Running Foot (As per required)
5.1	Network Switch	Web-managed PoE switch with 8 100M ports PoE + 2 ports COMBO Power Switch max : 123W 802.3af/at PoE standard; Data monitor and control. VLAN configurable; Port trunk; STP, multicast and port mirroring. With 2U Rack and Power Extension Board, Etc...
5.2	Network Switch	Web-managed PoE switch with 16 100M ports PoE + 2 ports COMBO Power Switch max : 230W 802.3af/at PoE standard; Data monitor and control. VLAN configurable; Port trunk; STP, multicast and port mirroring. With 2U Rack and Power Extension Board, Etc...

5.3	Network Switch	5 Port Giga Switch 10/100/1000
6.1	LED 40"	40 Inch LED, 1920x1080 resolution with HDMI and official warranty
7.2	UPS / Battery	Branded 2 KVA UPS With 2 x Branded Acid Battery 230 Amp (27 Plats) with Installation 12U Cabinet Rack - Dust proof with Fan, power supply and all fitting arrangements.
8	Complete installation	IP CCTV Camera and Cabling electric wiring Installation, Testing, Commissioning, Staff Training, Delivery and Traveling, Programming and Handing Over of Complete System (Per Institute)

| colspan=17 | Procurement of CCTV Surveillance system |

S.No	Name of Institute	Total No's of Camera	indoor Camera : 30M IR	Outdoor Camera : 80M IR	16 Channel NVR	32 Channel NVR	64 Channel NVR	4TB HD	08 Port Switches	16 Port Switches	Network 05 Port Switches	1 KVA UPS / 200Amp ×01 Batt	2 KVA UPS / 200Amp x2 Batt	40" LED	Approx; Cabling 90RFT Per Camera
colspan=3	Department Requirments (Servey Report)		colspan=2	CCTV Camera's		colspan=3	Network Video Recoder		Hard Disk	colspan=3	Network Switches		colspan=2	Power Backup	Display	Cable

colspan=17 style="text-align:center"	**Procurement of CCTV Surveillance system**

Department Requirments (Servey Report)			**CCTV Camera's**		**Network Video Recoder**			**Hard Disk**	**Network Switches**			**Power Backup**		**Display**	**Cable**
S.No	**Name of Institute**	**Total No's of Camera**	**indoor Camera : 30M IR**	**Outdoor Camera : 80M IR**	**16 Channel NVR**	**32 Channel NVR**	**64 Channel NVR**	**4TB HD**	**08 Port Switches**	**16 Port Switches**	**Network 05 Port Switches**	**1 KVA UPS / 200Amp ×01 Batt**	**2 KVA UPS / 200Amp x2 Batt**	**40" LED**	**Approx; Cabling 90RFT Per Camera**
1	GTVC(boys) summer bagh dir (lower)	30	20	10	×	1	×	2	×	2	1	×	1	1	2700
2	GTVC(boys) Ghaznikhel Lakki Marwat	14	10	4	1	×	×	1	2	×	1	1	×	1	1260
3	GTVC (boys) Dargai Malakand	39	27	12	×	×	1	2	1	2	1	×	1	1	3510
4	GTVC (W) Totanto Banda Swat	7	5	2	1	×	×	1	1	×	×	1	×	1	630
5	GTVC(women) timergara dir (lower)	10	8	2	1	×	×	1	2	×	1	1	×	1	900
	BoQ	100	70	30	3	1	1	7	6	4	4	3	2	5	9000